Email ID: sdevsd.cwc@gmail.com

Phone & Fax: - 0680-2404285

भारत सरकार/Government of India

केन्द्रीय जल आयोग/Central Water Commission

उप- मंडलीय अभियंता का कार्यालय/O/o Sub Divisional Engineer

वंशधारा उप-मंडल/Vamsadhara Sub Division

सिटी कॉलेज के पास, आम्बपुआ/Near City college, Ambapua

ब्रह्मपुर (ओडिशा)/Brahmapur -760 011 (Odisha)

क्रमसंख्या: वीएसडी/ टी-8/2025/ 493-97 (H) **दिनांक: 10/12/2025**

कोटेशन आमंत्रण सूचना
(ई- कोटेशन)

भारत के राष्ट्रपति के ओर से अधोहस्ताक्षरी द्वारा नीचे दिए गए नियमों और शर्तों के अधीन निम्नलिखित कार्यों के लिए वास्तविक/ प्राधिकृत/ सरकार द्वारा अनुमोदित ठेकेदारों/ फर्मों/ एजेंसियों से मुहरबंद कोटेशन आमंत्रित किए जाते हैं।

कार्य का नाम	अनुमानित लागत (रु.)	बयाना राशि (ई.एम.डी.)	कोटेशन जमा करने की अंतिम तिथि एवं समय	कोटेशन खोलने की तिथि एवं समय	कार्य का स्थान/ स्थिति
"Repair and transfer of office building and construction of GI sheet wall of site Kashinagar under VSD, CWC, Berhampur"	2,32,964/-	4,660/-	18.12.2025 16:00 Hrs O/o The Sub-divisional Engineer, Vamsadhara Sub-division, CWC, Berhampur-760011	19.12.2025 11:00 Hrs O/o Executive Engineer, Eastern Rivers Division, CWC, Bhubaneswar - 751022 (Odisha)	GDSQ Site Office, Central Water Commission, Near Sri Ram Degree College, At/Po-Kashinagar, Dist- Gajapati, Odisha-761206

विधिवत हस्ताक्षरित कोटेशन को किसी भी वाणिज्यिक बैंक के बीमा ज़मानत बांड/ डिमांड ड्राफ्ट/ अकाउंट पेयी बैंकर्स चेक/ एफ.डी.आर/ बैंक गारंटी (किसी एक) के रूप में ऊपर उल्लिखित रुपये की बयाना राशि (ई.एम.डी.) के साथ **अधिशासी अभियंता, पूर्वी नदियाँ मण्डल , भुवनेश्वर के पक्ष में जमा किया जाना चाहिए**। सूक्ष्म और लघु उद्यमों (एम.एस.ई.) से ई.एम.डी. भुगतान की छूट के लिए प्रमाण पत्र संलग्न करने का अनुरोध किया जाता है। कोटेशन केवल EMD या MSE प्रमाणपत्र (यदि लागू हो) के साथ ही स्वीकार्य होगा।

नियम एवं शर्तें:-

1. कोटेशन वाले लिफाफे के ऊपर **"Repair and transfer of office building and construction of GI sheet wall of site Kashinagar under VSD, CWC, Berhampur"** लिखा होना चाहिए।
2. कोटेशन को ठेकेदारों/ फर्मों/ एजेंसियों के लेटर पैड में मात्रा और दरों की अनुसूची के लिए दिये गए निर्धारित प्रो-फॉर्मा (अनुलग्नक- I) में डाक के माध्यम से या सीधे **उप- मंडलीय अभियंता का कार्यालय, वंषधारा उप-मंडल, सिटी कॉलेज के पास, आम्बपुआ, ब्रह्मपुर (ओडिशा)** के निविदा/ कोटेशन बॉक्स में जमा किया जाना चाहिए।
3. दरें GST तथा सभी करों सहित उद्धृत की जानी चाहिए। अन्य कोई भी शुल्क अलग से स्वीकार नहीं किया जाएगा।
4. दरें एफ.ओ.आर. सी.डब्ल्यू.सी. कार्यस्थल **GDSQ Site Office, Central Water Commission, Near Sri Ram Degree College, At/Po- Kashinagar, Dist- Gajapati, Odisha- 761206** में गंतव्य और डिलीवरी के रूप में उद्धृत की जानी चाहिए।
5. दरें कोटेशन खुलने की तारीख से 120 दिनों (न्यूनतम) के लिए वैध होनी चाहिए।
6. दरें अंकों के साथ-साथ शब्दों में भी उद्धृत की जानी चाहिए।
7. अधोहस्ताक्षरी के पास बिना कोई कारण बताए कोटेशन के एक हिस्से या पूरे को अस्वीकार करने का अधिकार सुरक्षित रहेगा।
8. असफल कोटेशनकर्ताओं/ बोलीदाताओं की सूचना संबंधित ठेकेदारों/ फर्मों/ एजेंसियों को नहीं दी जाएगी और उनका इन विषय पर इस कार्यालय पर किसी भी प्रकार का कोई दावा नहीं रहेगा।
9. सभी कटिंग/ओवर-राइटिंग पर ठेकेदारों/ फर्मों/ एजेंसियों या ठेकेदारों/ फर्मों/ एजेंसियों के अधिकृत व्यक्तियों द्वारा हस्ताक्षर किए जाने चाहिए।
10. प्रत्यक्ष या अप्रत्यक्ष किसी भी रूप में प्रचार करना सख्त वर्जित है।
11. एजेंसी के पास वैध PAN और GST पंजीकरण संख्या होनी चाहिए और उसकी प्रति कोटेशन के साथ जमा की जानी चाहिए।
12. प्रस्तावित कार्य की मात्रा किसी भी समय (कार्य आदेश जारी/ कार्य निष्पादन के दौरान) घटाई या बढ़ाई जा सकती है, जिसके लिए एजेंसी कार्य आदेश के अनुसार अनुमोदित दरों पर कार्य करने के लिए बाध्य रहेंगे।
13. सी.पी.डब्ल्यू.डी. (CPWD) के सभी नियम/ मैनुअल/ एस.ओ.पी. और इसमें लागू होने वाले संशोधन बोलीदाताओं पर बाध्यकारी होंगे।
14. यदि बोलीदाता या उनके प्रतिनिधि चाहें तो कोटेशन के उद्घाटन में शामिल हो सकते हैं।
15. यदि कोटेशन खोलने की तारीख छुट्टी/ कार्यालय बंद होने के दिन या अधिकारी की अनुपलब्धता के अंतर्गत आती है, तो कोटेशन अगले उपलब्ध कार्य दिवस पर खोली जाएगी।
16. यह NIQ केंद्र सरकार के ई-प्रकाशन पोर्टल (URL- https://eprocure.gov.in/epublish/app) पर प्रकाशित किया गया है।

बि. बि. बलबंतराय

(बिस्वबिनायक बलबंतराय)
उप-मंडलीय अभियंता,
वंषधारा उप-मंडल,
के.ज.आयोग, ब्रह्मपुर ।

प्रतिलिपि:

1. अधीक्षण अभियंता, जल विज्ञानीय प्रेक्षण परिमंडल, केन्द्रीय जल आयोग, भुवनेश्वर।
2. अधिशासी अभियंता, पूर्वी नदियाँ मंडल, केन्द्रीय जल आयोग, भुवनेश्वर।
3. सहायक लेखा अधिकारी, पूर्वी नदियाँ मंडल, केन्द्रीय जल आयोग, भुवनेश्वर।
4. सुचना पट, वंषधारा उप-मंडल, केन्द्रीय जल आयोग, ब्रह्मपुर।
5. एस. एम. निदेशालय, नई दिल्ली (केन्द्रीय जल आयोग के पोर्टल पर अपलोड करने हेतु)।

Email ID: sdevsd.cwc@gmail.com

Phone & Fax: - 0680-2404285

भारत सरकार/Government of India
केन्द्रीय जल आयोग/Central Water Commission
उप- मंडलीय अभियंता का कार्यालय/O/o Sub Divisional Engineer
वंशधारा उप-मंडल/Vamsadhara Sub Division
सिटी कॉलेज के पास, आम्बपुआ/Near City college, Ambapua
ब्रहमपुर (ओडिशा)/Brahmapur -760 011 (Odisha)

NO: VSD/T-8/2025/ 86-90 (E) **Date: 10/12/2025**

NOTICE INVITING QUOTATION
(e- NIQ)

On behalf of the President of India, sealed quotations are invited by the undersigned from the bonafide/ authorized/ Govt. approved contractors/ firms/ agencies for the following work(s) subject to the terms and conditions given below.

Name of the work	Estimated Cost (Rs.)	EMD (Rs.)	Last date & time for submission	Date & time of opening	Location / situation of the work
"Repair and transfer of office building and construction of GI sheet wall of site Kashinagar under VSD, CWC, Berhampur"	2,32,964/-	4,660/-	18.12.2025 16:00 Hrs O/o The Sub-divisional Engineer, Vamsadhara Sub-division, CWC, Berhampur-760011	19.12.2025 11:00 Hrs O/o Executive Engineer, Eastern Rivers Division, CWC, Bhubaneswar - 751022 (Odisha)	GDSQ Site Office, Central Water Commission, Near Sri Ram Degree College, At/Po-Kashinagar, Dist-Gajapati, Odisha-761206

The quotation(s) (duly signed) should be submitted with an Earnest Money Deposit (EMD) of rupees mentioned above in form of the Insurance Surety Bond/ Demand Draft/ Account Payee Banker's Cheque / FDR/ Bank Guarantee (any one) of any commercial Bank in favour of **Executive Engineer, Eastern Rivers Division and payable at Bhubaneswar**. Micro and Small Enterprises (MSEs) are requested to enclose certificate(s) for exemption of EMD payment. Quotation shall only acceptable with EMD or MSE certificate (if applicable).

Terms & Conditions:-

1. The envelope containing quotation should be super scribed as **"Repair and transfer of office building and construction of GI sheet wall of site Kashinagar under VSD, CWC, Berhampur".**
2. The quotations should be submitted in the prescribed pro-forma for Schedule of Quantities and Rates **(Annexure- I)** in the letter pad of the contractors/ firms/ agencies through post or directly in the Tender/ Quotation Box of **O/o The Sub-divisional Engineer,**

Vamsadhara Sub-division, Central Water Commission, Near City College, Ambapua, Berhampur, Odisha-760011.

3. The rates should be quoted inclusive of all taxes including GST and no charges shall be accepted separately in other forms.
4. The rates are to be quoted F.O.R. destination and delivery at **GDSQ Site Office, Central Water Commission, Near Sri Ram Degree College, At/Po- Kashinagar, Dist- Gajapati, Odisha- 761206**.
5. The rates shall be valid for 120 days (minimum) from the date of opening of the quotation.
6. The rates are to be quoted in figures as well as in words.
7. The undersigned reserves the right to reject a part or the whole of quotation without assigning any reason thereof.
8. Intimation to the unsuccessful quotationers/ bidders will not be given to the concerned contractors/ firms/ agencies and they shall have no claim on this office in any nature.
9. All cuttings/ over-writing should be initialled by the contractors/ firms/ agencies or authorize persons of the contractors/ firms/ agencies.
10. Canvassing in any form whether directly or indirectly is strictly prohibited.
11. The agency shall have valid PAN and GST Registration number and the copy of the same should be submitted with the quotation(s).
12. The quantity of the proposed work may be decreased or increased at any time (during issue of work order/ execution of work) for which the agency will be bound to do the work on approved rates as per work order.
13. All the Rules/Manuals/ SoPs of CPWD and its amendments as applicable will be binding on the bidders.
14. The bidders or their representative may attend the opening of quotations, if they wish so.
15. If the date of opening of quotation(s) falls under holiday/ closed day of office or non-availability of officer(s), the quotation(s) shall be opened on the next available working day.
16. This NIQ is published in Central Govt. e- publishing portal (at URL- https://eprocure.gov.in/epublish/app).

10.12.2025

Sub- Divisional Engineer
Vamsadhara Sub-Division
Central Water Commission
Berhampur

Copy to:-

1. The Superintending Engineer, HOC, CWC, Bhubaneswar
2. The Executive Engineer, Eastern Rivers Division, Central Water Commission, Bhubaneswar.
3. The Assistant Accounts Officer, Eastern Rivers Division, CWC, Bhubaneswar
4. Notice Board of VSD, CWC, Berhampur.
5. The SM Dte. CWC, New Delhi for uploading in CWC portal.

Annexure- I

मात्रा और दरों की अनुसूची / Schedule of Quantities and Rates

S.N.	Description	Unit	QTY	Rate in Rs. (Including GST)	
				In Figures	In Words
1	Providing and injecting approved grout in proportion recommended by the manufacturer into cracks/honey-comb area of concrete/masonry by suitable gun/pump at required pressure including cutting of nipples after curing etc. complete as per directions of Engineer-in-Charge. (The payment shall be made on the basis of actual weight of approved grout injected.Epoxy injection grout in concrete/RCC work of approved make.	kg	54.900		
2	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes , finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with : 12.5 mm thick tapered edge gypsum plain board conforming to IS: 2095- (Part I) :2011 (Board with BIS certification marks).	sqm	12.250		

3	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required: White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests.	Each	1.000		
4	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Surgeon type wash basin of size 660x460 mm with a pair of 15 mm C.P. brass pillar taps with elbow including operated levers	Each	1.000		
5	Centrifugally SCI(spun) S & S P or S trap.	Each	3.000		
6	Weeding out of lawn by removal of all weeds and other wild growth with roots by forking including disposal of garden rubbish with all loads and lifts complete if top dressing requried (cost of manure, sludge or extra good earth to be paid for separately) as per direction and satisfaction of officer in charge Where weeds upto 50%.	sqm	1300.000		
7	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.In cement mortar.	cum	9.488		
8	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-incharge. All kinds of soil.	cum	0.480		
9	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	cum	0.480		
10	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	kg	368.798		
11	Providing and fixing asbestos sheet in boundary wall with accessories	sqm	8.800		
12	Providing and fixing precoated galvanised steel sheet roofing accessories 0.50 mm (+0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete : Ridges plain (500 - 600mm) in boundary wall.	sqm	33.000		
13	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed steel conduit, with piano type switch, phenolic laminated sheet, suitable size MS box and earthing the point with 1.5 sq.mm FRLS PVC	Points	8.000		

	insulated copper conductor single core cable etc. as required. Group C				
14	Supply, Installation, Testing and Commissioning of 1200 mm sweep, BEE 5 star rated, ceiling fan with Brush Less Direct Current (BLDC) Motor, class of insulation: B, 3 nos. blades, 30 cm long down rod, 2 nos. canopies, shackle kit, safety rope, copper winding, Power Factor not less than 0.9, Service Value (CMM/W) minimum 6.85, Air delivery minimum 215 CMM, 350 RPM (tolerance as per IS : 374-2019), THD less than 10%, remote or electronic regulator unit for speed control and all remaining accessories including safety pin, nut bolts, washers, temperature rise=75 degree C (max.), insulation resistance more than 2 mega ohm, suitable for 230 V, 50 Hz, single phase AC Supply, earthing etc. complete as required.	Each	1.000		
15	Grading roof for water proofing treatment with Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size)	Cum	1.830		

***