भारत सरकार
जल शक्ति मंत्रालय
जल संसाधनए नदी विकास एवं
गंगा संरक्षण विभाग
केंद्रीय जल आयोग
उत्तर पूर्वी अन्वेषण मण्डल-II

Government of India
Ministry of Jal Shakti
Dept. of Water Resources, RD&GR
Central Water Commission
North East Investigation Division-II

NEID-II/HQ/NIQ(Vol-10)/2024-25/868-69

Date:10/12/2025

NOTICE INVITING QUOTATION

For and on behalf of the President of India, sealed quotations are invited by the undersigned from the authorized / reputed contractor/firms for the work of **"Construction/ Repair and Maintenance of Retaining wall of Boundary of MISD, Serchhip, Mizoram."** The Sealed Quotation will be received in the office of undersigned i.e. O/o Executive Engineer, NEID-II, CWC, Aizawl during working hours up to 14:30 hrs. on or before 18/12/2025 & shall be opened on same day by 15:30 hrs. by the undersigned/authorized official in presence of interested quotations or their authorized representatives who desired to remain present at the time of opening of quotations.

Description of the work.	Estimate cost	Last date & time for receiving quotation.	Date & time for opening quotation	Location
Repair and Maintenance of MTBM at MAT-II (GD), Tlabung (GD), Mateshwari (GDSQ), Hruitezawl (GD) Pangkhua (GD) & Archung (GD) Sites under MISD, CWC, Serchhip, Mizoram.	1,95,695/-	18/12/2025 14:30	18/12/2025 15:30	NEID-II, CWC, Aizawl

10/12/2025

(Nishant Kumar)
Executive Engineer
NEID-II, CWC, Aizawl

Copy along with copies of quotation for information and wide circulation to:

1. The Accounts Branch, NEID-II, CWC, Aizawl.
2. Notice Board.

जलशक्तिपुरम,जेमबवक
आईजॉल ,मिजोरम -796017
ई मेल: neid2-cwc@gov.in

Jalshaktipuram, Zemabawk
Aizawl, Mizoram-796017
E-mail: neid2-cwc@gov.in

Schedule of Quantities

Subject: - Construction/ Repair and Maintenance of Retaining wall of Boundary of MISD, Serchhip, Mizoram.

Sl. No.	Description of work	Unit	Qty.	Rate (in Rs.)	Amount. (in Rs.)
1.	Earth work by mechanical/manual means in rough excavation, banking excavated earth in layers not exceeding 20cm in depth, breaking clods, watering, rolling each layer with ½ tonne roller or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up in embankments for roads, flood banks, marginal banks and guide banks or filling up ground depressions, lead up to 50 m and for all lift:	Cum	7.60		
2.	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering (1 cement: 1.5 coarse: 3 graded stone aggregate 20 mm nominal size derived from natural sources)	Cum	0.95		
3.	Random rubble masonry with hard stone in superstructure above plinth level and up to five floor level, including levelling up with the cement concrete 1:6:12 (1 Cement: 6 coarse:12 graded stone aggregate20 mm nominal size)	Cum	19.92		
	Total				

Signature of Bidder with Seal