भारत सरकार
जल शक्ति मंत्रालय
जल संसाधन नदी विकास एवं गंगा संरक्षण विभाग
केंद्रीय जल आयोग
पी० सी० पी० निदेशालय

सत्यमेव जयते

Government of India
Ministry of Jal Shakti
Dept. of Water Resources, RD&GR
Central Water Commission
PCP Directorate

03/R&MofLib/2015-PCP / **Dated- 25.11.2025**

NOTICE INVITING QUOTATION

Sub: NIQ for Cleaning of Sewer Line, Water Tank and some miscellaneous work of Library & Information Bureau Building, CWC, New Delhi- reg.

Quotations are invited for Cleaning of Sewer Line, Water Tank and some miscellaneous work of Library & Information Bureau Building, CWC, New Delhi as per various items mentioned in below table at CWC (HQ). The quotations are submitted to the undersigned on or before 03.12.2025 upto 10:00 Hrs and shall be opened on the same day at 10.30 Hrs in the office of Deputy Director , Room No-214, PCP Directorate, Central Water Commission, 2nd Floor(S), Sewa Bhawan, R.K. Puram, New Delhi-110066.

S. No.	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
1	Cleaning of terrace/loft water storage tank (inside surface area) upto 2000 litre capacity at all heights with coconut brushes, duster etc., removal of silt, rubbish from the tank and cleaning the tank with fresh water disinfecting with bleaching powder @ 0.5gm per litre capacity of tank including marking the date of cleaning on the side of tank body with the help of stencil and paint and disposing of malba all complete as per direction of Engineer in-Charge. (The old date already written on tank should be removed with paint remover or black paint and if date is not written with the stencil or old date is not removed deduction will be made @ Rs. 0.10 per litre) (if during cleaning any GI fittings or ball cock is damaged that is to be repaired by contractor at his own cost and nothing extra will be paid on this account)	litre	2,16,000.00		
2	Cleaning of chocked sewer line by diesel running vehicle mounting hydraulic operated high pressure suction cum jetting sewer cleaning machine fitted with pump having 4000 litres suction capacity and 6000 litres water jetting tank capacity including skilled operator, supervising engineer etc. for cleaning and partial desilting of manholes and dechocking of sewer lines. Dechocking and flushing of sewer line from one manhole to another by high pressure jetting system of 2200 PSI for sewer line from 150 mm dia upto 300 mm	meter	165.00		
3	Cleaning and desilting of gully trap chamber, including removal of rubbish mixed with earth etc. and disposal of same, all as per the direction of Engineer-in-charge.	nos.	16.00		

द्वितीय तल (दक्षिण), सेवा भवन
राम कृष्ण पुरम, नई दिल्ली -110066
दूरभाष: 011-29583232

2nd Floor (South), Sewa Bhawan
R.K. Puram, New Delhi -110066
Tel: 011-29583232

भारत सरकार
जल शक्ति मंत्रालय
जल संसाधन नदी विकास एवं गंगा संरक्षण विभाग
केंद्रीय जल आयोग
पी० सी० पी० निदेशालय

सत्यमेव जयते

Government of India
Ministry of Jal Shakti
Dept. of Water Resources, RD&GR
Central Water Commission
PCP Directorate

4	Taking out C.I. cover with frame from R.C.C. top slab of manholes of various sizes including demolishing of R.C.C. work manually/ by mechanical means and stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead as per direction of Engineer-in-charge.	nos.	16.00		
5	Dismantling of road gully chamber of various sizes including C.I. grating with frame including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead including refilling the excavated gap.	nos.	16.00		
6	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.15.2.1 Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	cum	0.20		
7	Providing and laying in position cement concrete of specified grade 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	1.47		
8	Providing and fixing in position pre-cast R.C.C. manhole cover and frame of required shape and approved quality, L D- 2.5, Rectangular shape 600x450 mm internal dimensions	each	14.00		
9	Providing and fixing in position pre-cast R.C.C. manhole cover and frame of required shape and approved quality, H D - 20, Circular shape 560 mm internal diameter	each	2.00		
10	Providing and fixing 2 mm thick 16 to 19 mm wide PVC edge binding tape of approved quality for cupboard/wardrobe shutters including necessary synthetic resin hot pressed to edges on binding machine etc. complete as per direction of Engineer-in-charge.	meter	500.00		
11	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand)	cum	0.94		

भारत सरकार
जल शक्ति मंत्रालय
जल संसाधन नदी विकास एवं गंगा संरक्षण विभाग
केंद्रीय जल आयोग
पी० सी० पी० निदेशालय

सत्यमेव जयते

Government of India
Ministry of Jal Shakti
Dept. of Water Resources, RD&GR
Central Water Commission
PCP Directorate

12	Disposal of moorum/building rubbish/ malba/ similar unserviceable, dismantled or waste material by mechanical transportincluding loading, transporting, unloading to approved municipal dumping ground for lead upto 10 km for all lifts, completeas per directions of Engineer-in-charge.	cum	40.00		
13	Providing and fixing plain lining with necessary screws/nuts & bolts/ nails, including a coat of approved primer on one face, and fixed on wooden /steel frame work, complete as per direction of Engineer-in- charge (Frame work shall be paid for separately) 12 mm thick commercial ply conforming to IS : 1328 BWR type table	sqm	38.37		
14	Providing & Fixing decorative high pressure laminated sheet of plain /wood grain in gloss / matt/ suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS : 2046 Type S, including cost of adhesive of approved quality 1.5 mm thick	sqm	38.37		
15	Providing, mixing and applying bonding coat of approved adhesive on chipped portion of RCC as per specifications and direction of Engineer In-charge complete in all respect Epoxy bonding adhesive having coverage 2.20 sqm/kg of approved make	sqm	11.00		
				Total	
Rs (in Words)					

Terms & Conditions:

1. The above work shall be done at environs of L&IB Building, CWC (HQ), Sewa Bhawan, R. K. Puram, Sector 1, New Delhi-110066.
2. The Bid should be sent in a properly sealed cover addressed to **Deputy Director, Room No-214, PCP Directorate, Central Water Commission, 2nd Floor(S), Sewa Bhawan, R.K. Puram, New Delhi-110066.**
3. The bidder must visit the office/site for any clarification regarding the samples/quantity or quality of the items mentioned above within the office hours before closing date of the NIQ.
4. The work shall be done immediately from the date of issue of the work order.
5. All materials and workmanship shall conform to CPWD specifications and Delhi Schedule of Rates (DSR) 2023, any deviation must be approved in writing by the competent authority.
6. The contractor shall also liaise with MCD and CPWD wherever deemed necessary for smooth execution.

भारत सरकार
जल शक्ति मंत्रालय
जल संसाधन नदी विकास एवं गंगा संरक्षण विभाग
केंद्रीय जल आयोग
पी० सी० पी० निदेशालय

सत्यमेव जयते

Government of India
Ministry of Jal Shakti
Dept. of Water Resources, RD&GR
Central Water Commission
PCP Directorate

7. The contractor shall provide all labor, materials, tools, and equipment necessary as per the technical specifications outlined in the NIQ.
8. The contractor shall adhere to the restrictions laid in Delhi-NCR time to time in line with the air quality. Any kind of penalty arises due to non-compliance of the restriction/guidelines issued by the State Govt or Central Govt shall be the full responsibility of the contractor.
9. Any legal action arises due to the fact of non-compliance of any of the State or Central Govt. policy/guideline etc shall be full responsibility of the contractor himself.
10. A defect liability period of 12 months from the date of completion shall apply. Any defects arising during this period shall be repaired by the contractor at no additional cost. Any deviation from this clause shall result in debarment or blacklisting from further working in Govt. organizations.
11. The bidder must be a registered contractor with CPWD and supporting document for the same shall be submitted with the NIQ.
12. Prices shall be quoted inclusive of all taxes, duties, and transportation etc. No extra payment from the quoted price shall be made in any case.
13. Any discrepancies arise due to calculation mistake of the total amount or rates, the minimum of all shall be taken as final for deciding the L1 bidder. If the bids become non responsive due to the calculation mistake those bid shall not be considered for evaluation.
14. The successful bidder must complete the work within the time frame of 15 days from the date of award of work order.
15. No extra cost or time extension shall be allowed on account of delay in obtaining any work permissions.
16. This office reserves the right to terminate the contract at any stage in case of non-performance or breach of terms, with appropriate deductions for the completed work.
17. The work shall be carried out in such a manner so as not to effect or disturb any services coming along the work.
18. The work carried out shall be managed by the contractor in accordance to the working hours of the offices so that minimum disturbance will be created to the officials.
19. Payment shall be made after successful completion of the work and upon verification by the competent authority and no advance payment shall be made.
20. No extra payment will be made for transportation and conveyance of the goods and labour etc.
21. The Undersigned reserves right to accept or reject any or all the quotation/s without assigning any reason.
22. The contractor shall ensure that no damage is caused to the equipment / Govt. building/ office in the performance of his services. Any loss suffered therein will be made good by the Contractor and CWC may recover from contractor's Final Bill. If the amount of the damage exceeds the quotation price then the bidder at his own cost will rectify all the damages to the satisfaction of the Engineer in charge.

भारत सरकार
जल शक्ति मंत्रालय
जल संसाधन नदी विकास एवं गंगा संरक्षण विभाग
केंद्रीय जल आयोग
पी० सी० पी० निदेशालय

सत्यमेव जयते

Government of India
Ministry of Jal Shakti
Dept. of Water Resources, RD&GR
Central Water Commission
PCP Directorate

23. On submission of pre-receipted bill in triplicate, payment will be made by through e-payment and no advance payment shall be made.

(Karan Raghuvanshi)
Deputy Director

Copy to:-

1. PAO, 8th floor, CWC, Sewa Bhawan, R. K. Puram, New Delhi-66.
2. DDO-II, 8th floor, CWC, Sewa Bhawan, R. K. Puram, New Delhi-66.
3. Notice Board, Sewa Bhawan & L&IB Building, CWC.