भारत सरकार
जल शक्ति मंत्रालय
जल संसाधन, नदी विकास और
गंगा संरक्षण विभाग
केंद्रीय जल आयोग
वैगई उपमन्डल

Government of India
Ministry of Jal Shakti
Department of Water Resources, River
Development& Ganga Rejuvenation
Central Water Commission
Vaigai Sub-division

प.स/Lr.No: VSD/T-1/09/01/2025/ 177-184

दिनांक/ Dated: 24th October, 2025

NOTICE INVITING QUOTATIONS

For and on behalf of the President of India, sealed quotations are invited by the undersigned from the authorized/reputed contractor/firms for the work of "Casting of R.C.C. Gauge Post and Installation of R.C.C. Gauge Post, Target pole, Pivot Pole, Name boards, Direction boards at Site Narikkalpatti under VSD, CWC, Madurai". The sealed quotation will be received in the office of undersigned i.e., O/o The Sub-Divisional Engineer, VSD, CWC, Madurai during working hours up to 15:00 hours on or before 24/10/2025 & shall be opened on same day by 15.30 hours by the undersigned/authorized official in presence of interested quotationers or their authorized representatives who desired to remain present at the time of opening of quotations.

Description of the work	Estimate cost	Last date & time for receiving quotation	Date & time for opening quotation	Location
Casting of R.C.C. Gauge Post and Installation of R.C.C. Gauge Post, Target pole, Pivot Pole, Name boards, Direction boards at Site Narikkalpatti under VSD, CWC, Madurai	Rs. 2,42,168/-	**11/11/2025** & 15.00 hrs	**11/11/2025** & 15.30 hrs	Vaigai Sub Division, CWC, Madurai.

भवदीय/Yours faithfully,

24/10/2025

(विपिन राज वी.यू/ Vipin Raj V.U)
उपमन्डलीय अभियन्ता/ Sub Divisional Engineer
वैगई उपमन्डल/ Vaigai Sub Division

Copy to:

1. The Executive Engineer, SRD, CWC, Coimbatore for kind information.
2. The Accounts Branch, SRD, CWC, Coimbatore.
3. The Software Management Directorate with request to upload in CWC Tender portal.
4. The Sub-divisional Engineer, MCSD/ Coimbatore & LCSD/ Trichy for information and with a request to display on notice board please.
5. The Junior Engineer (HQs), VSD, CWC, Madurai.
6. The Junior Engineer/ Site in-charge, Site Balasamudram, VSD, CWC.
7. Notice board, CWC, Madurai.

त.ना.हा.बो.कॉलोनी,सेक्टर I & II,
तमिल नगर, आनायूर डा.घ.,
मदुरै- 625017
दूरभाष : 0452-2661348
ईमेल: vaigaisubdiv-cwc@gov.in
♦जल संरक्षण-जीवन संरक्षण♦

TNHB Colony, Sector I & II,
Tamil Nagar, Anaiyur P.O.,
Madurai - 625017
Tel: 0452-2661348
email: vaigaisubdiv-cwc@gov.in
♦Conserve Water - Save Life ♦

Annexure -I

PRICE BID

Casting of R.C.C. Gauge Post and Installation of R.C.C. Gauge Post, Target pole, Pivot Pole, Name boards, Direction boards at Site Narikkalpatti under VSD, CWC, Madurai

Sl.No.	Description	Qty	Unit	Rate	Amount
Repair Works					
1	Clearing jungle including uprooting of rank vegetation, grass, brush wood, tress and saplings of girth upto 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	873.00	sqm		
2	Earthwork in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 Sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer in charge.	6.564	cum		
3	Earthwork in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 Sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer in charge.	0.820	cum		
4	Providing and laying in position cement concrete of specified grade: 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources) excluding the cost of centering and shuttering - All work up to plinth level.	7.232	cum		
5	Providing, transporting, hoisting and fixing above plinth level up to floor five level precast reinforced cement concrete in Gauge post, individually or forming box louvers, setting in cement mortar 1:2 (1 cement : 2 coarse sand), including the cost of required centering, shuttering & smooth finishing but ,excluding the cost of reinforcement, with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	0.705	cum		
6	Steel Reinforcement for R.C.C. work including Straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	121.34	kg		
7	Binding Wire	5	kg		
8	Shuttering oil	10	lit		

Sl.No.	Description	Qty	Unit	Rate	Amount
9	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In stringers, treads, landings etc. of stair cases, including use of chequered plate wherever required, all complete.	835.411	kg		
10	Gauge post Finishing walls with Acrylic Smooth exterior paint of required shade :New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm).(As per directed by Engineers Incharge)	23.558	sqm		
11	Structural steel frame and sheet Painting with synthetic enamel paint of approved brand and manufacture to give an even shade:Two or more coats on new work.	22.545	sqm		

Name & Signature of Bidder

Limited Tender Form

Name of the Procuring Entity: ***The Sub-Divisional Engineer, Vaigai Sub-Division, Central Water Commission, Madurai.***

Firm's Reference		**Date**	
Firm Registration No. (if any)		PAN (attach photocopy)	
TIN/VAT/GST No.		***LIMITED TENDER FORM***	Address: **Office of the Sub-Divisional Engineer,** Vaigai Sub-Division, Central Water Commission, TNHB Colony, Sector I & II, Tamil Nagar, Anaiyur Post, Madurai - 625017 e-mail : vaigaisubdiv-cwc@gov.in
Phone			
Fax			
Email			
M/s:		Enquiry No. and Date	VSD/T-1/09/01/2025/ 177-184 Date : 24.10.2025
		Date of Tender Opening	**11/11/2025** at 15.30 hrs
		The tender would be opened at 15.30 Hrs on the date of tender opening above, at the address mentioned above.	

Limited tender form can be downloaded from **www.cwc.gov.in**

Please submit on or before 15.00 Hrs on the date of tender opening, your quotation for the following works, in accordance with the terms and conditions printed overleaf, in a sealed cover, marked on topwith – Enquiry No; Date of Tender Opening.

Yours Sincerely

Sub-Divisional Engineer,
Vaigai Sub-Division,
Central Water Commission,
Madurai.

Tender Schedule: All Rates in Figures and in Words in Rupees

Casting of R.C.C. Gauge Post and Installation of R.C.C. Gauge Post, Target pole, Pivot Pole, Name boards, Direction boards at Site Narikkalpatti under VSD, CWC, Madurai

Sl. No	Description and Specification	Qty.	Unit	Performance terms	Rate per Unit	Taxes & Duties	Packing / forwarding/ If any	Total Amount
1	Clearing jungle including uprooting of rank vegetation, grass, brush wood, tress and saplings of girth upto 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	873.00	Sqm	As per SOP of work and in accordance with the direction given by Engineer-in-charge				

2	Earthwork in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 Sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer in charge.	6.564	Cum	-do-				
3	Earthwork in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 Sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer in charge.	0.820	Cum	-do-				
4	Providing and laying in position cement concrete of specified grade: 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources) excluding the cost of centering and shuttering - All work up to plinth level.	7.232	Cum	-do-				
5	Providing, transporting, hoisting and fixing above plinth level up to floor five level precast reinforced cement concrete in Gauge post, individually or forming box louvers, setting in cement mortar 1:2 (1 cement : 2 coarse sand), including the cost of required centering, shuttering & smooth finishing but ,excluding the cost of reinforcement, with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	0.705	Cum	-do-				
6	Steel Reinforcement for R.C.C. work including Straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	121.34	kg	-do-				
7	Binding Wire	5	kg	-do-				
8	Shuttering oil	10	lit	-do-				
9	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In stringers, treads, landings etc. of stair cases, including use of chequered plate wherever	835.411	kg	-do-				

	required, all complete.							
10	Gauge post Finishing walls with Acrylic Smooth exterior paint of required shade :New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm).(As per directed by Engineers Incharge)	23.558	Sqm	do-				
11	Structural steel frame and sheet Painting with synthetic enamel paint of approved brand and manufacture to give an even shade:Two or more coats on new work.	22.545	Sqm	-do-				
				Total				

Total amount in words	

Performance Schedule: 60 days from issue of work order.

Specifications/Special Conditions of Contract: work should be performed as per CPWD manual/specification & direction of Engineer-in-charge.

Item/Tender Specific Conditions of this Tender:

I/we engage to performance the works to your office and comply the following:

1. Tender schedule and technical specification indicated.
2. Item/tender specific conditions for this tender.
3. Terms and conditions printed overleaf.
4. General conditions of contract signed by me at the time of supplier registration (for registered suppliers).
5. I/we confirm that set off for the GST, etc. Paid on the inputs have been taken into consideration in the above quoted price and further agree to pass on such additional duties as sets offs as may become available in future under GST, etc.
6. This offer is valid for 90 (ninety) days from the date of opening of the quotations.
7. That we have not been debarred by any Government/Undertaking.
8. That the rates quoted are not higher than the rates quoted for same item to any Government / Undertaking.
9. That the bid submitted by us is properly sealed and prepared so as to prevent any subsequent alteration and replacement.

Signature & Seal Place & Date:		**Name of Authorized Signatory:**	
Address:		**Tel. No./ Fax. No./ Mobile No.** **Email Id:**	

TERMS AND CONDITIONS OF LIMITED TENDER

i) The quotation must be in the form furnished by procuring entity and should be free from corrections/erasures. In case there is any unavoidable correction it should be properly attested. If not the quotation will not be considered. Quotation written in pencil will not be considered.

ii) Quotation will be opened on due date at 15.30 Hrs at the indicated venue in presence of the entities or their representatives who may wish to be present.

iii) The Government of India reserves the right to accept the offer by individual items and reject any or all tenders without assigning any reason thereof and does not bind itself to accept lowest quotations.

iv) Participation in this tender is by invitation only and is limited to the reputed entity involved in similar type of work. Unsolicited offers are liable to be ignored. However, relevant entity who desire to participate in such tenders in future may bring it to the notice of procuring entity and apply for registration as per procedure.

v) Complete details and specification if any must accompany the quotation. If you have got any counter offer as suitable to the material required by us, the same may be shown separately.

vi) The Government of India reserves the right to modify the work specified in this enquiry.

vii) The prices quoted should be firm till the works are completed. Please quote the rates in words and figures. Price quoted should be net and valid for a minimum period of three months from the date of opening of the quotation.

viii) Payment of GST is primarily the responsibility of the seller and will not be paid unless the percentage value is clearly mentioned in the quotations. If no indication regarding GST is recorded in the quotation, the GST will be considered as included.

ix) No advance payment will be made.

x) The performance period required for completion of work should be invariably specified in the quotation.

xi) In case your quotation is accepted and order is placed on you, the work completion against the order should be made within the period stipulated in the order. The Government of India reserves the right to recover any loss sustained due to delayed completion of work by way of penalty. Failure to performance of work within the stipulated period shall entitle Procuring Entity for the imposition of penalty without assigning any reasons @ 0.5% of the total value of the item covered in order as penalty per day subject to a maximum of 5% (five percent) unless extension is obtained in writing from the office on valid ground before expiry of performance period.

xii) Security deposit @ 2.5% will be deducted from total bill amount and released after 6 months from the date of completion of works.

xiii) Labour cess @1% will be deducted in the gross amount payable to Tamil Nadu Labour welfare Board, Government of Tamil Nadu.

xiv) The quotationers may visit the site before submitting quotation of the above work.

xv) Dispute clause: Any dispute arising on the contractor will be referred to the Superintending Engineer, Cauvery and Southern Rivers Circle, CWC, Coimbatore and decision of Superintending Engineer, Cauvery and Southern Rivers Circle, CWC, Coimbatore will be final and binding to the bidder.

xvi) Our normal payment will be made to the contractor on satisfactory completion of work on submission of pre-receipted bill in triplicate with mandate form, payment will be made by through e-payment PFMS/RTGS.

29/10/2021

Sub-Divisional Engineer,
Vaigai Sub-Division,
Central Water Commission,
Madurai.