भारतसरकार
जलशक्तिमंत्रालय
जलसंसाधननदीविकासएवंगंगासंरक्षणविभाग
केंद्रीय जल आयोग
कार्यालय, कार्यपालक अभियंता
महानदी मंडल

Government of India
Ministry of Jal Shakti
Dept. of Water Resources, RD&GR
Central Water Commission
Office of the Executive Engineer
Mahanadi Division

संख्या : म॰म॰/मुख्य /अन॰आई॰क्यू/2025-26/1751-1755 दिनांक:- 10/12/2025

NOTICE INVITING QUOTATION/उद्धरण आमंत्रण सूचना

Sealed Quotations are hereby invited by the Executive Engineer, Mahanadi Division, CWC, Burla on the behalf of the President of India from the Central Govt. / State Govt. / PSUs/ Co-operative societies registered contractors who have carried out similar works in othergovt. offices and PSUs as per details, terms and conditions given below for "**False Celling, Colour, Tiles Work, Renovation of Bathroom and Main Gate at VIP Transit Room, Office Building at UMSD, Raipur" with estimated cost of Rs.1,87,359/- (Rupees One Lakh Eighty Seven Thousand Three Hundred Fifty Nine Only) including GST** as per Annexure-1 enclosed herewith. The Quotations shall be received at Mahanadi Division, CWC, Burla up to **16:00 Hrs** on **24.12.2025** and will be opened on the same date at **16:30 hrs**. The interested representative of bona fide contractor/firm submitting Quotations may attend the office during opening of Quotations.

S.No	Name of items	Qty	Unit	Rate in Rs.	Amount	Remarks
	List with description has been enclosed.					

Terms & conditions

1. Sealed envelope containing the quotation along with the covering letter of firm/ agency should be subscripted as "Quotation for "**False Celling, Colour, Tiles Work, Renovation of Bathroom and Main Gate at VIP Transit Room, Office Building at UMSD, Raipur**" and addressed to the Executive Engineer, Mahanadi Division, Central Water Commission, Doctors' Colony, At & P.O. - Burla, District – Sambalpur (Odisha), PIN – 768017
2. Rate per unit should be quoted in Words as well as figures.
3. Rates should be inclusive of all taxes.
4. Each page should be signed and stamped by the agency.
5. All duties, taxes (including GST), transportation and other levies payable by the agency under the contract shall be included in the total price. Any damage or loss occurred during the process should be borne by the agency itself.
6. All the cutting and overwriting should be initialed by Quotationer.
7. If the opening date happens to be a holiday under any circumstances the Quotation will be opened on the next working day.
8. The undersigned reserves the right to reject any or all the Quotations without assigning or any reason thereof.
9. Quotationer must submit valid work license copy along with the quotation document.
10. Payment will be credited through e-payment (PFMS) to bank account for which Bank mandate form need to be provided along with bill, challan etc. at the time of supply of materials.
11. The Contractor must have valid PAN Card & GST Registration Certificate and ITR for last three Financial Year. (Copy should be enclosed along with Quotations).

डॉक्टर्स कॉलोनी, पो.- बुर्ला
जिला- संबलपुर ओड़िशा
दूरभाष:0663-2430238
ईमेल:eemdcwcburla@yahoo.co.in

At- Doctor's Colony, PO- Burla
Distt. - Sambalpur Odisha-768017
Tel: 0663-2430238,
E-mail: eemdcwcburla@yahoo.co.in

भारतसरकार
जलशक्तिमंत्रालय
जलसंसाधननदीविकासएवंगंगासंरक्षणविभाग
केंद्रीय जल आयोग
कार्यालय, कार्यपालक अभियंता
महानदी मंडल

सत्यमेव जयते

Government of India
Ministry of Jal Shakti
Dept. of Water Resources, RD&GR
Central Water Commission
Office of the Executive Engineer
Mahanadi Division

12. The Bid will be valid for 60days.
13. The Quotationer must enclose the e-procurement copy of advertisement along with Quotations./ website: www.eprocure.gov.in/epublish/app
14. The work shall be completed in 3months from issue of order from the office.

जि- अनंत साई
अधिशासी अभियंता
महानदी मण्डल सीडबल्यूसी बुरला
भारत के राष्ट्रपति के ओर से

Copy to:
1. The Superintending Engineer, HOC, CWC, Bhubaneswar for kind information please.
2. The Sub-Divisional Engineer, Upper Mahanadi Sub-Division, CWC, Raipur.
3. The Accounts Branch, MD, CWC, Burla.
4. Notice Board.
5. SMD for publishing in postal

डॉक्टर्स कॉलोनी, पो.- बुर्ला
जिला- संबलपुर ओडिशा
दूरभाष:0663-2430238
ईमेल:eemdcwcburla@yahoo.co.in
· जलसंरक्षण - सुरक्षित जीवन ·

At- Doctor's Colony, PO- Burla
Distt. - Sambalpur Odisha-768017
Tel: 0663-2430238,
E-mail: eemdcwcburla@yahoo.co.in
· Conserve Water- Save Life ·

भारतसरकार
जलशक्तिमंत्रालय
जलसंसाधननदीविकासएवंगंगासंरक्षणविभाग
केंद्रीय जल आयोग
कार्यालय, कार्यपालक अभियंता
महानदी मंडल

सत्यमेव जयते

Government of India
Ministry of Jal Shakti
Dept. of Water Resources, RD&GR
Central Water Commission
Office of the Executive Engineer
Mahanadi Division

Annexure-1

BOQ for False Celling, Colour, Tiles Work, Renovation of Bathroom and Main Gate at VIP Transit Room, Office Building at UMSD, Raipur.

SL. NO	Name of items	Unit	Quantity (nos)	Rate in Rs	Amount in Rs.	Remark
1	Dismantling false ceiling including disposal of unserviceable material and stacking of serviceable material within 50 meters lead as directed by Engineer in-charge.	L.S	1			
2	Providing and fixing false ceiling at all heights including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gsm/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide × 1.6 mm thick with flanges of 27 mm and 37 mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia × 50 mm long with 6 mm dia bolts, other flange of cleat fixed to the angle hangers of 25×10×0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45×15×0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia × 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of raw plugs at 450 mm centre, with 25 mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 × 25	Sqm	22.815			

डॉक्टर्स कॉलोनी, पो.- बुर्ला
जिला- संबलपुर ओडिशा
दूरभाष:0663-2430238
ईमेल:eemdcwcburla@yahoo.co.in
· जलसंरक्षण - सुरक्षित जीवन ·

At- Doctor's Colony, PO- Burla
Distt. - Sambalpur Odisha-768017
Tel: 0663-2430238,
E-mail: eemdcwcburla@yahoo.co.in
· Conserve Water- Save Life ·

	mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes , finishing with jointing compound in 3 layers covering up to 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with :					
	Fully Perforated Gypsum Plaster Board of size 1200 × 2400×12.5 mm having approx. 15% perforated area with perforation size and pattern as approved by the Engineer-in-charge and as per manufacturer and which includes providing and fixing of board with perimeter channel, intermediate channel, ceiling section, all complete as per specification and direction of the Engineer-in-charge, but excluding the cost of painting. The board should be manufactured from factory having ISO : 9001 and ISO :14001 certification and also having perforation tested as per ASTM standards and guaranteed by manufacturer to achieve NRC value not less than 0.60.					
3	Distempering with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gram/litre, of approved manufacturer and of required shade and colour all complete to achieve even shade and colour :	Sqm	22.815			
	New work (two or more coats) over and including water thinnable priming coat with cement primer having VOC					

	content less than 50 gram/litre					
4	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc.					
	Group A Light point (controlled by one switch).	Point	10			
	Group B Fan point (incl. regulator).	Point	1			
5	"Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required."	Qntl	1.02			
	2 Way 5/6 A Switch	Each	40			
	1 5/16 A Switch	Each	5			
	3 pin 5/6 A Socket outlet	Each	20			
	6 pin 1 5/16 A Socket	Each	5			
6	Wiring for circuit/ sub main wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required.					
	2 x 1.5 sq. mm + 1 x 1.5 sq. mm earth wire	meter	25.000			
	2 x 2.5 sq. mm + 1 x 2.5 sq. mm earth wire	meter	20.000			
	2 x 4 sq. mm + 1 x 4 sq. mm earth wire	meter	15.000			

7	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	Each	2			
8	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.	Each	1			
	2 single pole and natural					
9	Rope Light	Meter	20			
	15 W LED light	Nos	12			
10	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	Sqm	140.915			
11	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. Meters and	Sqm	7.046			
	under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement : 4 fine sand)					
12	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	Sqm	115.935			

13	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour.	Sqm	115.935			
14	Finishing walls with textured exterior paint of required shade Old work (One or more coats applied @ 1.82 ltr/10 sqm.	Sqm	24.980			
15	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in -charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	Sqm	0.351			
16	Demolishing tile work in floors and roofs laid in cement mortar including stacking material within 50 meters lead.	Sqm	13.5			
17	Providing and fixing Ist quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	Sqm	19.35			
18	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead : Of area 3 sq. metres and below	Sqm	2.28			

19	Guest Room Door of UMSD Providing and fixing aluminum work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminum sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminum snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :					
	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately)DSR2023-Vol-II-21.1.2 (II) Powder coated aluminum (minimum thickness of powder coating 50 micron)	Kg	19.2			
20	Providing and fixing ISI marked aluminum butt hinges anodized (anodic coating not less than grade AC 10 as per IS: 1868) transparent or dyed to required colour or shade with necessary screws etc. complete:	Each	8			

21	Providing and fixing aluminum tower bolts, ISI marked, anodized (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :300x10 mm	Each	2			
22	Providing and fixing aluminum handles, ISI marked, anodized (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 125mm	Each	4			
23	Providing and fixing aluminum hanging floor door stopper, ISI marked, anodized (anodic coating not less than grade AC 10 as per IS: 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete. Twin rubber stopper.	Each	2			
24	Providing and fixing Brass 100 mm mortice latch and lock with 6 levers without pair of handles (best make of approved quality) for aluminum doors including necessary cutting and making good etc. complete	Each	1			
25	Exhaust Fan for Bathroom	Each	1			
	Geyser for Bathroom	Each	1			

जे.अनंत साई
अधिशासी अभियन्ता
Executive Engineer
महानदी मंडल/Mahanadi-Div...
के.ज.आयोग, बुर्ला/CWC, Burla